Commissioning GFCA-Y2-A5-R Broj artikla: 8105389





Tehnički podaci

Svojstvo	Vrijednost
Scope of services	Data backup and documentation
	Introduction to WebVisu software
	Configuration and parameterisation
	Remote support during commissioning
	System test
	Checking the electrical connections and the travel path
Work involved on site	3 working hours
Customer requirements	Qualified personnel responsible for the machine present on the agreed
	date
	YJKP kit must be assembled mechanically
	24 V logic and 230/400 V load voltage must be made available
	Switch and Ethernet cable must be available
	Local installation of FFT software (see Support Portal)
	Local administrator rights
	Local installation of TeamViewer or Bomgar communication software
	Stable Internet connection
Provision of services	8-10 days subject to agreement