

Commissioning GFCA-Y2-A5

Part number: 8105388

FESTO



Data sheet

Feature	Value
Scope of action	Data backup and documentation Introduction to WebVisu software Configuration and parameterisation System test Checking the electrical connections and the travel path Support with electrical cabling On-site support during commissioning
Work involved on site	5 working hours
Customer requirements	Qualified personnel responsible for the machine must be present on the agreed date YJKP kit must be assembled mechanically 24 V logic and 230/400 V load voltage must be made provided Switch and Ethernet cable must be available
Provision of services	8-10 days subject to agreement