

Commissioning GFCA-Y2-A5

№ изделия: 8105388

FESTO



Таблица данных

| Характеристика | Значение |
|-----------------------|--|
| Scope of services | Data backup and documentation Introduction to WebVisu software Configuration and parameterisation System test Checking the electrical connections and the travel path Support with electrical cabling On-site support during commissioning |
| Work involved on site | 5 working hours |
| Customer requirements | Qualified personnel responsible for the machine present on the agreed date YJKP kit must be assembled mechanically 24 V logic and 230/400 V load voltage must be made available Switch and Ethernet cable must be available |
| Provision of services | 8-10 days subject to agreement |