

Commissioning

GFCA-Y2-A5

Broj artikla: 8105388

FESTO



Tehnički podaci

Svojstvo	Vrijednost
Scope of services	Data backup and documentation Introduction to WebVisu software Configuration and parameterisation System test Checking the electrical connections and the travel path Support with electrical cabling On-site support during commissioning
Work involved on site	5 working hours
Customer requirements	Qualified personnel responsible for the machine present on the agreed date YJKP kit must be assembled mechanically 24 V logic and 230/400 V load voltage must be made available Switch and Ethernet cable must be available
Provision of services	8-10 days subject to agreement