

Commissioning GFCH-3

Part number: 8044341

FESTO



Data sheet

Feature	Value
Structural design	Triple axis system
Scope of services	Activation of the axes in test mode Data backup and documentation Instruction of machine operators, e.g. in error diagnostics and eliminating errors or in changing the position values Configuration and parameterization of the axes Optimization of control parameters and homing Checking of wiring, connections, travel paths and energy chains
Work involved on site	7 hours of work
Customer requirements	Use of Festo components Access to the machine or system Mechanical, pneumatic and electrical work is completed Qualified personnel responsible for the machine must be present on the agreed date
Provision of services	8-10 days subject to agreement